

**Tender Details**

**Tender Code : 32821-OT**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
1	LIA600-10	600VA LIA UPS with 10minutes backup		3,820.00	5.00	0.00
2	LIA600-30	600 VA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		7,589.00	5.00	0.00
3	LIA1000-30	1 KVA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		12,600.00	5.00	0.00
4	LIA1000-30-IC	Installation charges for 1KVA LIA UPS with 30 minutes backup		150.00	0.00	15.00
5	LIA1000-60	1 KVA LIA UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		16,600.00	5.00	0.00
6	LIA1000-60-IC	Installation charges for 1KVA LIA UPS with 60 minutes backup		150.00	0.00	15.00
7	LIA1000-120	1 KVA LIA UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		25,350.00	5.00	0.00
8	LIA1000-120-IC	Installation charges for 1KVA LIA UPS with 120 minutes backup		150.00	0.00	15.00
9	LIA1000-240	1 KVA LIA UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		42,850.00	5.00	0.00
10	LIA1000-240-IC	Installation charges for 1KVA LIA UPS with 240 minutes backup		150.00	0.00	15.00
11	OL1000-30	1 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		16,575.00	5.00	0.00
12	OL1000-30-IC	Installation charges for 1 KVA On-Line UPS with 30 minutes backup		200.00	0.00	15.00
13	OL1000-60	1 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		22,500.00	5.00	0.00
14	OL1000-60-IC	Installation charges for 1 KVA On-Line UPS with 60 minutes backup		200.00	0.00	15.00
15	OL1000-120	1 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		29,249.00	5.00	0.00
16	OL1000-120-IC	Installation charges for 1 KVA On-Line UPS with 120 minutes backup		200.00	0.00	15.00
17	OL1000-240	1 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		55,450.00	5.00	0.00
18	OL1000-240-IC	Installation charges for 1 KVA On-Line UPS with 240 minutes backup		200.00	0.00	15.00
19	OL2000-30	2 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		28,800.00	5.00	0.00
20	OL2000-30-IC	Installation charges for 2KVA On-Line UPS with 30 minutes backup		400.00	0.00	15.00
21	OL2000-60	2 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		43,775.00	5.00	0.00
22	OL2000-60-IC	Installation charges for 2 KVA On-Line UPS with 60 minutes backup		400.00	0.00	15.00
23	OL2000-120	2 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		61,600.00	5.00	0.00
24	OL2000-120-IC	Installation charges for 2 KVA On-Line UPS with 120 minutes backup		400.00	0.00	15.00

**Tender Details**

**Tender Code : 32821-OT**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
25	OL2000-240	2 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		90,550.00	5.00	0.00
26	OL2000-240-IC	Installation charges for 2 KVA On-Line UPS with 240 minutes backup		450.00	0.00	15.00
27	OL3000-30	3 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		33,550.00	5.00	0.00
28	OL3000-30-IC	Installation charges for 3 KVA On-Line UPS with 30 minutes backup		450.00	0.00	15.00
29	OL3000-60	3 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		51,500.00	5.00	0.00
30	OL3000-60-IC	Installation charges for 3 KVA On-Line UPS with 60 minutes backup		450.00	0.00	15.00
31	OL3000-120	3 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		75,450.00	5.00	0.00
32	OL3000-120-IC	Installation charges for 3 KVA On-Line UPS with 120 minutes backup		450.00	0.00	15.00
33	OL3000-240	3 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		1,38,550.00	5.00	0.00
34	OL3000-240-IC	Installation charges for 3 KVA On-Line UPS with 240 minutes backup		450.00	0.00	15.00
35	OL5000-30	5 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		64,475.00	5.00	0.00
36	OL5000-30-IC	Installation charges for 5 KVA On-Line UPS with 30 minutes backup		800.00	0.00	15.00
37	OL5000-60	5 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		87,500.00	5.00	0.00
38	OL5000-60-IC	Installation charges for 5 KVA On-Line UPS with 60 minutes backup		800.00	0.00	15.00
39	OL5000-120	5 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		1,37,200.00	5.00	0.00
40	OL5000-120-IC	Installation charges for 5 KVA On-Line UPS with 120 minutes backup		800.00	0.00	15.00
41	OL5000-240	5 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		2,37,450.00	5.00	0.00
42	OL5000-240-IC	Installation charges for 5 KVA On-Line UPS with 240 minutes backup		800.00	0.00	15.00
43	OL-10K-30	10 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		1,20,900.00	5.00	0.00
44	OL-10K-30-IC	Installation charges for 10 KVA Online UPS Systems 30 Minutes Backup		800.00	0.00	15.00
45	OL-10K-60	10 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		1,66,300.00	5.00	0.00
46	OL-10K-60-IC	Installation charges for 10 KVA Online UPS Systems 60 Minutes Backup		800.00	0.00	15.00
47	OL-10K-120	10 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		2,53,500.00	5.00	0.00
48	OL-10K-120-IC	Installation charges for 10 KVA Online UPS Systems 120 Minutes Backup		800.00	0.00	15.00

**Tender Details**

Tender Code : 32821-OT

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
49	OL-15K-30	15 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		1,64,800.00	5.00	0.00
50	OL-15K-30-IC	Installation charges for 15 KVA Online UPS Systems 30 Minutes Backup		800.00	0.00	15.00
51	OL-15K-60	15 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		2,16,300.00	5.00	0.00
52	OL-15K-60-IC	Installation charges for 15 KVA Online UPS Systems 60 Minutes Backup		800.00	0.00	15.00
53	OL-15K-120	15 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		3,44,400.00	5.00	0.00
54	OL-15K-120-IC	Installation charges for 15 KVA Online UPS Systems 120 Minutes Backup		800.00	0.00	15.00
55	OL-20K-30	20 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		1,83,300.00	5.00	0.00
56	OL-20K-30-IC	Installation charges for 20 KVA Online UPS Systems 30 Minutes Backup		800.00	0.00	15.00
57	OL-20K-60	20 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		2,59,400.00	5.00	0.00
58	OL-20K-60-IC	Installation charges for 20 KVA Online UPS Systems 60 Minutes Backup		800.00	0.00	15.00
59	OL-20K-120	20 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		4,27,400.00	5.00	0.00
60	OL-20K-120-IC	Installation charges for 20 KVA Online UPS Systems 120 Minutes Backup		800.00	0.00	15.00
61	1151a	2 KVA UPS: Input Isolator with MS Enclosure 15-A - 2 pole		732.00	5.00	0.00
62	1151b	2 KVA UPS: Input Wiring: Cable: 2.5 Sq.mm - 2 Run & 1.5Sq.mm 1Run		98.00	5.00	0.00
63	1151c	2 KVA UPS: Output MCB with Enclosure 10 A - Double Pole		725.00	5.00	0.00
64	1151d	2 KVA UPS: Output Wiring Cable Details 2.5 Sq.mm - 3 Run		148.00	5.00	0.00
65	1152a	3 KVA UPS: Input Isolator with MS Enclosure 32-A - 2 pole		600.00	5.00	0.00
66	1152b	3 KVA UPS: Input Wiring: Cable: 4.0 Sq.mm - 2Run & 2.5 Sq.mm 1Run		168.00	5.00	0.00
67	1152c	3 KVA UPS: Output MCB with Enclosure 15 A - Double Pole		600.00	5.00	0.00
68	1152d	3 KVA UPS: Output Wiring Cable Details 2.5Sq.mm - 3 Run		148.00	5.00	0.00
69	1153a	5 KVA UPS: Input Isolator with MS Enclosure 40-A - 2 pole		790.00	5.00	0.00
70	1153b	5 KVA UPS: Input Wiring: Cable: 6.0 Sq.mm - 2 Run & 4.0 Sq.mm 1Run		247.00	5.00	0.00
71	1153c	5 KVA UPS: Output MCB with Enclosure 25 A - Double Pole		595.00	5.00	0.00
72	1153d	5KVA UPS: Output Wiring Cable Details 4.0Sq.mm - 3 Run		175.00	5.00	0.00
73	1156	5A-3pin Switches & Sockets 1 No with Gang box		145.00	5.00	0.00
74	1157	5A-3pin Switches & Sockets 1 set (1 Set = 3Nos.) with Gang box		200.00	5.00	0.00



**Tender Details**

Tender Code : 32821-OT

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
75	1158	15A Plug & Socket with box		275.00	5.00	0.00
76	1159	Earthing for 2.0 kva & 3.0 kva		4,490.00	5.00	0.00
77	1160	Earthing for 5.0 kva		5,490.00	5.00	0.00
78	1161	Earthing Wiring with 4.0 sqmm		98.00	5.00	0.00
79	1162	Earthing wiring with 6sq.mm cable for 5.0 kva.		118.00	5.00	0.00
80	UPSW-012a	10KVA UPS - Input Isolator with MS Enclosure 32A-4 Pole		944.00	5.00	0.00
81	UPSW-012b	10KVA - Input Wiring: Cable 6.0 Sq.mm: 5 Run		283.00	5.00	0.00
82	UPSW-012c	10KVA - Output MCB with Enclosure 50A Double Pole		890.00	5.00	0.00
83	UPSW-012d	10KVA - Output Wiring Cable Details 10.0 Sq.mm 2 Run & 6.0 Sq.mm 1 Run		186.00	5.00	0.00
84	UPSW-012e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box.		148.00	5.00	0.00
85	UPSW-012f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
86	UPSW-012g	15A Plug & Socket with Box		248.00	5.00	0.00
87	UPSW-012h	Earthing for 10 kva - Earthing for 10 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,950.00	5.00	0.00
88	UPSW-012i	Earthing wiring with 6 sq.mm cable 10 kva ups		39.00	5.00	0.00
89	UPSW-013a	15KVA UPS - Input isolator with MS Enclosure 40A 4 Pole		1,062.00	5.00	0.00
90	UPSW-013b	15KVA UPS - Input Wiring: Cable 10.0 Sq.mm 5 Run		401.00	5.00	0.00
91	UPSW-013c	15KVA UPS - Output MCB with Enclosure 63A/80A Double Pole		1,295.00	5.00	0.00
92	UPSW-013d	15KVA UPS - Output Wiring Cable Details 25.0 Sq.mm - 2 Run & 10.0 Sq.mm 1 Run		499.00	5.00	0.00
93	UPSW-013e	Switches & Sockets 5A-3Pin Switches & Sockets 1 No. with Gang Box		150.00	5.00	0.00
94	UPSW-013f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
95	UPSW-013g	15A Plug & Socket with box		275.00	5.00	0.00
96	UPSW-013h	Earthing for 15 KVA - Earthing for 15 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided		6,000.00	5.00	0.00

**Tender Details**

Tender Code : 32821-OT

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
		with funnel and copper bar. (including Civil work)				
97	UPSW-013i	Earthing: Earthing wiring with 10 sq.mm cable 15 kva ups	.	71.00	5.00	0.00
98	UPSW-014a	20KVA UPS - Input Isolator with MS Enclosure 63A 4 Pole	.	500.00	5.00	0.00
99	UPSW-014b	20KVA UPS - Input Wiring: Cable: 16.0 Sq.mm 5 Run	.	625.00	5.00	0.00
100	UPSW-014c	20KVA UPS - Output MCB with Enclosure 100A Double Pole	.	1,000.00	5.00	0.00
101	UPSW-014d	20KVA UPS - Output Wiring Cable Details 25.0 Sq.mm 2 Run & 10.0 Sq.mm 1 Run	.	487.00	5.00	0.00
102	UPSW-014e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box	.	148.00	5.00	0.00
103	UPSW-014f	5A-3Pin Switches & Sockets 1 Set with Gang Box	.	150.00	5.00	0.00
104	UPSW-014g	15A Plug & Socket with Box	.	275.00	5.00	0.00
105	UPSW-014h	Earthing for 20 kva - Earthing for 20 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,990.00	5.00	0.00
106	UPSW-014i	Earthing Wiring with 16 Sq.mm cable 20 KVA UPS	.	100.00	5.00	0.00

Tender Code : 32821-OT

Supplier : V0214A~UNILINE ENERGY SYSTEMS P LTD

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
1	LIA600-10	600VA LIA UPS with 10minutes backup	Make : UnilineModel : Smartline 60012V/17AH -1Nos.(OR) 12V/7AH 2nos. (Hi Power/ Relicel/ Okaya/Global/Base)	3,820.00	5.00	0.00
2	LIA600-30	600 VA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : UnilineModel : Smartline 60012V/18AH - 2Nos.(Okaya/Global/Quanta/Base)	7,589.00	5.00	0.00
3	LIA1000-30	1 KVA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : UnilineModel : Smartline 100012V/33AH 2Nos. (OR) 12V/65AH 1no.(Hi Power/ Relicel/ Okaya/Global/Base)	12,600.00	5.00	0.00
4	LIA1000-30-IC	Installation charges for 1KVA LIA UPS with 30 minutes backup		150.00	0.00	15.00
5	LIA1000-60	1 KVA LIA UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : UnilineModel : Smartline 100012V/65AH - 2Nos.(Hi Power/ Relicel/ Okaya/Global/Base)	16,600.00	5.00	0.00
6	LIA1000-60-IC	Installation charges for 1KVA LIA UPS with 60 minutes backup		150.00	0.00	15.00
7	LIA1000-120	1 KVA LIA UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Smarline 1000 12V/130AH - 2Nos (Hi Power/ Relicel/ Okaya/Global/Base)	25,350.00	5.00	0.00
8	LIA1000-120-IC	Installation charges for 1KVA LIA UPS with 120 minutes backup		150.00	0.00	15.00

**Tender Details**

Tender Code : 32821-OT

Supplier : V0214A~UNILINE ENERGY SYSTEMS P LTD

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
9	LIA1000-240	1 KVA LIA UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Smarline 1000 12V/130AH - 4Nos (Hi Power/ Relicel/ Okaya/Global/Base)	42,850.00	5.00	0.00
10	LIA1000-240-IC	Installation charges for 1KVA LIA UPS with 240 minutes backup		150.00	0.00	15.00
11	OL1000-240	1 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 1000 12V/100AH - 6Nos (Hi Power/ Relicel/ Global/Okaya/Base)	55,450.00	5.00	0.00
12	OL1000-240-IC	Installation charges for 1 KVA On-Line UPS with 240 minutes backup	.	200.00	0.00	15.00
13	OL2000-30	2 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 2000 12V/33AH - 4Nos (Hi Power/ Relicel/ Okaya/Global/Base)	28,800.00	5.00	0.00
14	OL2000-30-IC	Installation charges for 2KVA On-Line UPS with 30 minutes backup	.	400.00	0.00	15.00
15	OL2000-60	2 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 2000 12V/45AH - 6Nos (Hi Power/ Relicel/ Okaya/Global/Base)	43,775.00	5.00	0.00
16	OL2000-60-IC	Installation charges for 2 KVA On-Line UPS with 60 minutes backup	.	400.00	0.00	15.00
17	OL2000-120	2 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 2000 12V/70AH - 8Nos (Hi Power/ Relicel/ Okaya/Global/Base)	61,600.00	5.00	0.00
18	OL2000-120-IC	Installation charges for 2 KVA On-Line UPS with 120 minutes backup	.	400.00	0.00	15.00
19	OL2000-240	2 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 2000 12V/130AH - 8Nos (Hi Power/ Relicel/ Okaya/Global/Base)	90,550.00	5.00	0.00
20	OL2000-240-IC	Installation charges for 2 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
21	OL3000-120	3 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 3000 12V/100AH - 8Nos (Hi Power/ Relicel/ Okaya/Global/Base)	75,450.00	5.00	0.00
22	OL3000-120-IC	Installation charges for 3 KVA On-Line UPS with 120 minutes backup	.	450.00	0.00	15.00
23	OL3000-240	3 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 3000 12V/100AH - 16Nos (Hi Power/ Relicel/ Okaya/Global/Base)	1,38,550.00	5.00	0.00
24	OL3000-240-IC	Installation charges for 3 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
25	OL5000-30	5 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 5000 12V/45AH - 15Nos (Hi Power/ Relicel/ Okaya/Global/Base)	64,475.00	5.00	0.00
26	OL5000-30-IC	Installation charges for 5 KVA On-Line UPS with 30 minutes backup	.	800.00	0.00	15.00
27	OL5000-60	5 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 5000 12V/45AH - 15Nos (Hi Power/ Relicel/ Okaya/Global/Base)	87,500.00	5.00	0.00
28	OL5000-60-IC	Installation charges for 5 KVA On-Line UPS with 60 minutes backup	.	800.00	0.00	15.00
29	OL5000-120	5 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 5000 12V/45AH - 30Nos (Hi Power/ Relicel/ Okaya/Global/Base)	1,37,200.00	5.00	0.00
30	OL5000-120-IC	Installation charges for 5 KVA On-Line UPS with 120 minutes backup	.	800.00	0.00	15.00
31	OL5000-240	5 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 5000 12V/100AH - 28Nos (Hi Power/ Relicel/ Okaya/Global/Base)	2,37,450.00	5.00	0.00
32	OL5000-240-IC	Installation charges for 5 KVA On-Line UPS with 240 minutes backup	.	800.00	0.00	15.00



**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0214A~UNILINE ENERGY SYSTEMS P LTD**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
33	OL-10K-30	10 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 10000 12V/26AH - 28Nos (Hi Power/ Relicel/ Okaya/Global/Base)	1,20,900.00	5.00	0.00
34	OL-10K-30-IC	Installation charges for 10 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
35	OL-10K-60	10 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 10000 12V/45AH - 30Nos (Hi Power/ Relicel/ Okaya/Global/Base)	1,66,300.00	5.00	0.00
36	OL-10K-60-IC	Installation charges for 10 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
37	OL-10K-120	10 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 10000 12V/45AH - 60Nos (Hi Power/ Relicel/ Okaya/Global/Base)	2,53,500.00	5.00	0.00
38	OL-10K-120-IC	Installation charges for 10 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
39	OL-15K-30	15 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 15000 12V/28AH - 60Nos (Hi Power/ Relicel/ Okaya/Global/Base)	1,64,800.00	5.00	0.00
40	OL-15K-30-IC	Installation charges for 15 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
41	OL-15K-60	15 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 15000 12V/75AH - 30Nos (Hi Power/ Relicel/ Okaya/Global/Base)	2,16,300.00	5.00	0.00
42	OL-15K-60-IC	Installation charges for 15 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
43	OL-15K-120	15 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 15000 12V/135AH - 30Nos (OR) 12V/130AH-32nos. (Hi Power/ Relicel/ Okaya/Global/Base)	3,44,400.00	5.00	0.00
44	OL-15K-120-IC	Installation charges for 15 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
45	OL-20K-30	20 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 20000 12V/42AH - 32Nos (Hi Power/ Relicel/ Okaya/Global/Base)	1,83,300.00	5.00	0.00
46	OL-20K-30-IC	Installation charges for 20 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
47	OL-20K-60	20 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 20000 12V/45AH - 64Nos (Hi Power/ Relicel/ Okaya/Global/Base)	2,59,400.00	5.00	0.00
48	OL-20K-60-IC	Installation charges for 20 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
49	OL-20K-120	20 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Uniline Model :Maxi Power 20000 12V/200AH - 28Nos (Hi Power/ Relicel/ Okaya/Global/Base)	4,27,400.00	5.00	0.00
50	OL-20K-120-IC	Installation charges for 20 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
51	1151a	2 KVA UPS: Input Isolator with MS Enclosure 15-A - 2 pole		732.00	5.00	0.00
52	1151b	2 KVA UPS: Input Wiring: Cable: 2.5 Sq.mm - 2 Run & 1.5Sq.mm 1Run		98.00	5.00	0.00
53	1151c	2 KVA UPS: Output MCB with Enclosure 10 A - Double Pole		725.00	5.00	0.00
54	1151d	2 KVA UPS: Output Wiring Cable Details 2.5 Sq.mm - 3 Run		148.00	5.00	0.00
55	1152a	3 KVA UPS: Input Isolator with MS Enclosure 32-A - 2 pole		600.00	5.00	0.00
56	1152b	3 KVA UPS: Input Wiring: Cable: 4.0 Sq.mm - 2Run & 2.5 Sq.mm 1Run		168.00	5.00	0.00
57	1152c	3 KVA UPS: Output MCB with Enclosure 15 A - Double Pole		600.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0214A~UNILINE ENERGY SYSTEMS P LTD**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
58	1152d	3 KVA UPS: Output WiringCable Details 2.5Sq.mm - 3 Run		148.00	5.00	0.00
59	1153a	5 KVA UPS: InputIsolator with MS Enclosure40-A - 2 pole		790.00	5.00	0.00
60	1153b	5 KVA UPS: Input Wiring:Cable: 6.0 Sq.mm - 2 Run & 4.0 Sq.mm 1Run		247.00	5.00	0.00
61	1153c	5 KVA UPS: Output MCBwith Enclosure 25 A - DoublePole		595.00	5.00	0.00
62	1153d	5KVA UPS: Output WiringCable Details 4.0Sq.mm - 3 Run		175.00	5.00	0.00
63	1156	5A-3pin Switches &Sockets 1 No with Gang box		145.00	5.00	0.00
64	1157	5A-3pin Switches &Sockets 1 set (1 Set = 3Nos.) with Gang box		200.00	5.00	0.00
65	1158	15A Plug & Socket with box		275.00	5.00	0.00
66	1159	Earthing for 2.0 kva &3.0 kva		4,490.00	5.00	0.00
67	1160	Earthing for 5.0 kva		5,490.00	5.00	0.00
68	1161	Earthing Wiring with4.0 sqmm		98.00	5.00	0.00
69	1162	Earthing wiring with 6sq.mm cable for 5.0 kva.		118.00	5.00	0.00
70	UPSW-012a	10KVA UPS - Input Isolator with MS Enclosure 32A-4 Pole		944.00	5.00	0.00
71	UPSW-012b	10KVA - Input Wiring: Cable 6.0 Sq.mm: 5 Run		283.00	5.00	0.00
72	UPSW-012c	10KVA - Output MCB with Enclosure 50A Double Pole		890.00	5.00	0.00
73	UPSW-012d	10KVA - Output Wiring Cable Details 10.0 Sq.mm 2 Run & 6.0 Sq.mm 1 Run		186.00	5.00	0.00
74	UPSW-012e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box.		148.00	5.00	0.00
75	UPSW-012f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
76	UPSW-012g	15A Plug & Socket with Box		248.00	5.00	0.00
77	UPSW-012h	Earthing for 10 kva - Earthing for 10 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,950.00	5.00	0.00
78	UPSW-012i	Earthing wiring with 6 sq.mm cable 10 kva ups		39.00	5.00	0.00
79	UPSW-013a	15KVA UPS - Input isolator with MS Enclosure 40A 4 Pole		1,062.00	5.00	0.00
80	UPSW-013b	15KVA UPS - Input Wiring: Cable 10.0 Sq.mm 5 Run		401.00	5.00	0.00
81	UPSW-013c	15KVA UPS - Output MCB with Enclosure 63A/80A Double Pole		1,295.00	5.00	0.00
82	UPSW-013d	15KVA UPS - Output Wiring Cable Details 25.0 Sq.mm - 2 Run & 10.0 Sq.mm 1 Run		499.00	5.00	0.00



**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0214A~UNILINE ENERGY SYSTEMS P LTD**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
83	UPSW-013e	Switches & Sockets 5A-3Pin Switches & Sockets 1 No. with Gang Box		150.00	5.00	0.00
84	UPSW-013f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
85	UPSW-013g	15A Plug & Socket with box		275.00	5.00	0.00
86	UPSW-013h	Earthing for 15 KVA - Earthing for 15 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		6,000.00	5.00	0.00
87	UPSW-013i	Earthing: Earthing wiring with 10 sq.mm cable 15 kva ups		71.00	5.00	0.00
88	UPSW-014a	20KVA UPS - Input Isolator with MS Enclosure 63A 4 Pole		500.00	5.00	0.00
89	UPSW-014b	20KVA UPS - Input Wiring: Cable: 16.0 Sq.mm 5 Run		625.00	5.00	0.00
90	UPSW-014c	20KVA UPS - Output MCB with Enclosure 100A Double Pole		1,000.00	5.00	0.00
91	UPSW-014d	20KVA UPS - Output Wiring Cable Details 25.0 Sq.mm 2 Run & 10.0 Sq.mm 1 Run		487.00	5.00	0.00
92	UPSW-014e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box		148.00	5.00	0.00
93	UPSW-014f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
94	UPSW-014g	15A Plug & Socket with Box		275.00	5.00	0.00
95	UPSW-014h	Earthing for 20 kva - Earthing for 20 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,990.00	5.00	0.00
96	UPSW-014i	Earthing Wiring with 16 Sq.mm cable 20 KVA UPS		100.00	5.00	0.00

**Tender Code : 32821-OT**

**Supplier : V0287~Novateur Electrical and Digital Systems Pvt. Ltd.,**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
1	LIA600-10	600VA LIA UPS with 10minutes backup	Make : Numeric, Model :Digital 600-EX12V/7AH 1No. SMF battery (Amaraja (Quanta)/Exide Power Safe/Numeric/Panasonic)	3,820.00	5.00	0.00
2	OL1000-240	1 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : NumericModel : Onfiniti 12V/100AH 6Nos. (OR) 12V/75AH 8nos. Amaron ( Quanta Make) /Exide/Power Safe/Numeric/Panasonic	55,450.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0287~Novateur Electrical and Digital Systems Pvt. Ltd.,**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
3	OL1000-240-IC	Installation charges for 1 KVA On-Line UPS with 240 minutes backup	.	200.00	0.00	15.00
4	OL2000-240	2 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : NumericModel : Onfiniti 12V/84AH 12Nos. (OR) 12V/65AH 16nos. Amaron (Quanta Make) /Exide/Power Safe/Numeric/Panasonic	90,550.00	5.00	0.00
5	OL2000-240-IC	Installation charges for 2 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
6	OL3000-120	3 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : NumericModel : Onfiniti 12V/100AH 8Nos. Amaron (Quanta Make) /Exide/Power Safe/Numeric/Panasonic	75,450.00	5.00	0.00
7	OL3000-120-IC	Installation charges for 3 KVA On-Line UPS with 120 minutes backup	.	450.00	0.00	15.00
8	OL3000-240	3 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : NumericModel : Onfiniti 12V/100AH 16Nos. Amaron (Quanta Make) /Exide/Power Safe/Numeric/Panasonic	1,38,550.00	5.00	0.00
9	OL3000-240-IC	Installation charges for 3 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
10	OL5000-120	5 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : NumericModel : Onfiniti 12V/84AH 16Nos. (OR) 12V/65AH 21nos. Amaron (Quanta Make) /Exide/Power Safe/Numeric/Panasonic	1,37,200.00	5.00	0.00
11	OL5000-120-IC	Installation charges for 5 KVA On-Line UPS with 120 minutes backup	.	800.00	0.00	15.00
12	OL5000-240	5 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : NumericModel : Onfiniti 12V/84AH 32Nos. Amaron (Quanta Make) /Exide/Power Safe/Numeric/Panasonic	2,37,450.00	5.00	0.00
13	OL5000-240-IC	Installation charges for 5 KVA On-Line UPS with 240 minutes backup	.	800.00	0.00	15.00
14	1151a	2 KVA UPS: Input Isolator with MS Enclosure 15-A - 2 pole		732.00	5.00	0.00
15	1151b	2 KVA UPS: Input Wiring: Cable: 2.5 Sq.mm - 2 Run & 1.5Sq.mm 1Run		98.00	5.00	0.00
16	1151c	2 KVA UPS: Output MCB with Enclosure 10 A - Double Pole		725.00	5.00	0.00
17	1151d	2 KVA UPS: Output Wiring Cable Details 2.5 Sq.mm - 3 Run		148.00	5.00	0.00
18	1152a	3 KVA UPS: Input Isolator with MS Enclosure 32-A - 2 pole		600.00	5.00	0.00
19	1152b	3 KVA UPS: Input Wiring: Cable: 4.0 Sq.mm - 2Run & 2.5 Sq.mm 1Run		168.00	5.00	0.00
20	1152c	3 KVA UPS: Output MCB with Enclosure 15 A - Double Pole		600.00	5.00	0.00
21	1152d	3 KVA UPS: Output Wiring Cable Details 2.5Sq.mm - 3 Run		148.00	5.00	0.00
22	1153a	5 KVA UPS: Input Isolator with MS Enclosure 40-A - 2 pole		790.00	5.00	0.00
23	1153b	5 KVA UPS: Input Wiring: Cable: 6.0 Sq.mm - 2 Run & 4.0 Sq.mm 1Run		247.00	5.00	0.00
24	1153c	5 KVA UPS: Output MCB with Enclosure 25 A - Double Pole		595.00	5.00	0.00
25	1153d	5KVA UPS: Output Wiring Cable Details 4.0Sq.mm - 3 Run		175.00	5.00	0.00
26	1156	5A-3pin Switches & Sockets 1 No with Gang box		145.00	5.00	0.00
27	1157	5A-3pin Switches & Sockets 1 set (1 Set = 3Nos.) with Gang box		200.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0287~Novateur Electrical and Digital Systems Pvt. Ltd.,**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
28	1158	15A Plug & Socket with box		275.00	5.00	0.00
29	1159	Earthing for 2.0 kva &3.0 kva		4,490.00	5.00	0.00
30	1160	Earthing for 5.0 kva		5,490.00	5.00	0.00
31	1161	Earthing Wiring with4.0 sqmm		98.00	5.00	0.00
32	1162	Earthing wiring with 6sq.mm cable for 5.0 kva.		118.00	5.00	0.00
33	UPSW-012a	10KVA UPS - Input Isolator with MS Enclosure 32A-4 Pole		944.00	5.00	0.00
34	UPSW-012b	10KVA - Input Wiring: Cable 6.0 Sq.mm: 5 Run		283.00	5.00	0.00
35	UPSW-012c	10KVA - Output MCB with Enclosure 50A Double Pole		890.00	5.00	0.00
36	UPSW-012d	10KVA - Output Wiring Cable Details 10.0 Sq.mm 2 Run & 6.0 Sq.mm 1 Run		186.00	5.00	0.00
37	UPSW-012e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box.		148.00	5.00	0.00
38	UPSW-012f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
39	UPSW-012g	15A Plug & Socket with Box		248.00	5.00	0.00
40	UPSW-012h	Earthing for 10 kva - Earthing for 10 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,950.00	5.00	0.00
41	UPSW-012i	Earthing wiring with 6 sq.mm cable 10 kva ups		39.00	5.00	0.00
42	UPSW-013a	15KVA UPS - Input isolator with MS Enclosure 40A 4 Pole		1,062.00	5.00	0.00
43	UPSW-013b	15KVA UPS - Input Wiring: Cable 10.0 Sq.mm 5 Run		401.00	5.00	0.00
44	UPSW-013c	15KVA UPS - Output MCB with Enclosure 63A/80A Double Pole		1,295.00	5.00	0.00
45	UPSW-013d	15KVA UPS - Output Wiring Cable Details 25.0 Sq.mm - 2 Run & 10.0 Sq.mm 1 Run		499.00	5.00	0.00
46	UPSW-013e	Switches & Sockets 5A-3Pin Switches & Sockets 1 No. with Gang Box		150.00	5.00	0.00
47	UPSW-013f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
48	UPSW-013g	15A Plug & Socket with box		275.00	5.00	0.00
49	UPSW-013h	Earthing for 15 KVA - Earthing for 15 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided		6,000.00	5.00	0.00



**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0287~Novateur Electrical and Digital Systems Pvt. Ltd.,**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
		with funnel and copper bar. (including Civil work)				
50	UPSW-013i	Earthing: Earthing wiring with 10 sq.mm cable 15 kva ups		71.00	5.00	0.00
51	UPSW-014a	20KVA UPS - Input Isolator with MS Enclosure 63A 4 Pole		500.00	5.00	0.00
52	UPSW-014b	20KVA UPS - Input Wiring: Cable: 16.0 Sq.mm 5 Run		625.00	5.00	0.00
53	UPSW-014c	20KVA UPS - Output MCB with Enclosure 100A Double Pole		1,000.00	5.00	0.00
54	UPSW-014d	20KVA UPS - Output Wiring Cable Details 25.0 Sq.mm 2 Run & 10.0 Sq.mm 1 Run		487.00	5.00	0.00
55	UPSW-014e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box		148.00	5.00	0.00
56	UPSW-014f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
57	UPSW-014g	15A Plug & Socket with Box		275.00	5.00	0.00
58	UPSW-014h	Earthing for 20 kva - Earthing for 20 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,990.00	5.00	0.00
59	UPSW-014i	Earthing Wiring with 16 Sq.mm cable 20 KVA UPS		100.00	5.00	0.00

**Tender Code : 32821-OT**

**Supplier : V0305~IGA TECH Industrial Electronics P Ltd**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
1	LIA1000-30	1 KVA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : IGA TECH, Model : IGLI1K-30 12V/75AH 1No. SMF battery (Exide/Quanta)	12,600.00	5.00	0.00
2	LIA1000-30-IC	Installation charges for 1KVA LIA UPS with 30 minutes backup		150.00	0.00	15.00
3	LIA1000-60	1 KVA LIA UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : IGA TECH, Model : IGLI1K-60 12V/130AH 1No. SMF battery (Exide/Quanta)	16,600.00	5.00	0.00
4	LIA1000-60-IC	Installation charges for 1KVA LIA UPS with 60 minutes backup		150.00	0.00	15.00
5	LIA1000-120	1 KVA LIA UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : IGA TECH, Model : IGLI1K-120-12V/130AH 2Nos. SMF battery (Exide/Quanta)	25,350.00	5.00	0.00
6	LIA1000-120-IC	Installation charges for 1KVA LIA UPS with 120 minutes backup		150.00	0.00	15.00
7	OL1000-240	1 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : IGA TECH, Model : IGOL1K-240-12V/130AH 4Nos. SMF battery (Exide/Quanta)	55,450.00	5.00	0.00
8	OL1000-240-IC	Installation charges for 1 KVA On-Line UPS with 240 minutes backup		200.00	0.00	15.00
9	OL3000-120	3 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : IGA TECH, Model : IGOL3K-120-12V/100AH 8Nos. SMF battery (Exide/Quanta)	75,450.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0305~IGA TECH Industrial Electronics P Ltd**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
10	OL3000-120-IC	Installation charges for 3 KVA On-Line UPS with 120 minutes backup	.	450.00	0.00	15.00
11	OL3000-240	3 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : IGA TECH, Model : IGOL3K-240-12V/100AH 16Nos. SMF battery (Exide/Quanta)	1,38,550.00	5.00	0.00
12	OL3000-240-IC	Installation charges for 3 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
13	OL5000-120	5 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : IGA TECH, Model : IGOL5K-120-12V/84AH 16Nos. SMF battery (Exide/Quanta)	1,37,200.00	5.00	0.00
14	OL5000-120-IC	Installation charges for 5 KVA On-Line UPS with 120 minutes backup	.	800.00	0.00	15.00
15	OL5000-240	5 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : IGA TECH, Model : IGOL5K-240-12V/84AH 32Nos. SMF battery (Exide/Quanta)	2,37,450.00	5.00	0.00
16	OL5000-240-IC	Installation charges for 5 KVA On-Line UPS with 240 minutes backup	.	800.00	0.00	15.00
17	OL-10K-30	10 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : IGA TECH, Model : IGOL10K-30-12V/42AH 16Nos. SMF battery (Exide/Quanta)	1,20,900.00	5.00	0.00
18	OL-10K-30-IC	Installation charges for 10 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
19	OL-10K-60	10 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : IGA TECH, Model : IGOL10K-60-12V/84AH 16Nos. SMF battery (Exide/Quanta)	1,66,300.00	5.00	0.00
20	OL-10K-60-IC	Installation charges for 10 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
21	OL-15K-30	15 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : IGA TECH, Model : IGOL15K-30-12V/65AH 16Nos. SMF battery (Exide/Quanta)	1,64,800.00	5.00	0.00
22	OL-15K-30-IC	Installation charges for 15 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
23	1151a	2 KVA UPS: Input Isolator with MS Enclosure 15-A - 2 pole		732.00	5.00	0.00
24	1151b	2 KVA UPS: Input Wiring: Cable: 2.5 Sq.mm - 2 Run & 1.5Sq.mm 1Run		98.00	5.00	0.00
25	1151c	2 KVA UPS: Output MCB with Enclosure 10 A - Double Pole		725.00	5.00	0.00
26	1151d	2 KVA UPS: Output Wiring Cable Details 2.5 Sq.mm - 3 Run		148.00	5.00	0.00
27	1152a	3 KVA UPS: Input Isolator with MS Enclosure 32-A - 2 pole		600.00	5.00	0.00
28	1152b	3 KVA UPS: Input Wiring: Cable: 4.0 Sq.mm - 2Run & 2.5 Sq.mm 1Run		168.00	5.00	0.00
29	1152c	3 KVA UPS: Output MCB with Enclosure 15 A - Double Pole		600.00	5.00	0.00
30	1152d	3 KVA UPS: Output Wiring Cable Details 2.5Sq.mm - 3 Run		148.00	5.00	0.00
31	1153a	5 KVA UPS: Input Isolator with MS Enclosure 40-A - 2 pole		790.00	5.00	0.00
32	1153b	5 KVA UPS: Input Wiring: Cable: 6.0 Sq.mm - 2 Run & 4.0 Sq.mm 1Run		247.00	5.00	0.00
33	1153c	5 KVA UPS: Output MCB with Enclosure 25 A - Double Pole		595.00	5.00	0.00
34	1153d	5KVA UPS: Output Wiring Cable Details 4.0Sq.mm - 3 Run		175.00	5.00	0.00
35	1156	5A-3pin Switches & Sockets 1 No with Gang box		145.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0305~IGA TECH Industrial Electronics P Ltd**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
36	1157	5A-3pin Switches &Sockets 1 set (1 Set = 3Nos.) with Gang box		200.00	5.00	0.00
37	1158	15A Plug & Socket with box		275.00	5.00	0.00
38	1159	Earthing for 2.0 kva &3.0 kva		4,490.00	5.00	0.00
39	1160	Earthing for 5.0 kva		5,490.00	5.00	0.00
40	1161	Earthing Wiring with4.0 sqmm		98.00	5.00	0.00
41	1162	Earthing wiring with 6sq.mm cable for 5.0 kva.		118.00	5.00	0.00
42	UPSW-012a	10KVA UPS - Input Isolator with MS Enclosure 32A-4 Pole		944.00	5.00	0.00
43	UPSW-012b	10KVA - Input Wiring: Cable 6.0 Sq.mm: 5 Run		283.00	5.00	0.00
44	UPSW-012c	10KVA - Output MCB with Enclosure 50A Double Pole		890.00	5.00	0.00
45	UPSW-012d	10KVA - Output Wiring Cable Details 10.0 Sq.mm 2 Run & 6.0 Sq.mm 1 Run		186.00	5.00	0.00
46	UPSW-012e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box.		148.00	5.00	0.00
47	UPSW-012f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
48	UPSW-012g	15A Plug & Socket with Box		248.00	5.00	0.00
49	UPSW-012h	Earthing for 10 kva - Earthing for 10 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,950.00	5.00	0.00
50	UPSW-012i	Earthing wiring with 6 sq.mm cable 10 kva ups		39.00	5.00	0.00
51	UPSW-013a	15KVA UPS - Input isolator with MS Enclosure 40A 4 Pole		1,062.00	5.00	0.00
52	UPSW-013b	15KVA UPS - Input Wiring: Cable 10.0 Sq.mm 5 Run		401.00	5.00	0.00
53	UPSW-013c	15KVA UPS - Output MCB with Enclosure 63A/80A Double Pole		1,295.00	5.00	0.00
54	UPSW-013d	15KVA UPS - Output Wiring Cable Details 25.0 Sq.mm - 2 Run & 10.0 Sq.mm 1 Run		499.00	5.00	0.00
55	UPSW-013e	Switches & Sockets 5A-3Pin Switches & Sockets 1 No. with Gang Box		150.00	5.00	0.00
56	UPSW-013f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
57	UPSW-013g	15A Plug & Socket with box		275.00	5.00	0.00
58	UPSW-013h	Earthing for 15 KVA - Earthing for 15 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of		6,000.00	5.00	0.00



**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0305~IGA TECH Industrial Electronics P Ltd**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
		Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)				
59	UPSW-013i	Earthing: Earthing wiring with 10 sq.mm cable 15 kva ups		71.00	5.00	0.00
60	UPSW-014a	20KVA UPS - Input Isolator with MS Enclosure 63A 4 Pole		500.00	5.00	0.00
61	UPSW-014b	20KVA UPS - Input Wiring: Cable: 16.0 Sq.mm 5 Run		625.00	5.00	0.00
62	UPSW-014c	20KVA UPS - Output MCB with Enclosure 100A Double Pole		1,000.00	5.00	0.00
63	UPSW-014d	20KVA UPS - Output Wiring Cable Details 25.0 Sq.mm 2 Run & 10.0 Sq.mm 1 Run		487.00	5.00	0.00
64	UPSW-014e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box		148.00	5.00	0.00
65	UPSW-014f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
66	UPSW-014g	15A Plug & Socket with Box		275.00	5.00	0.00
67	UPSW-014h	Earthing for 20 kva - Earthing for 20 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,990.00	5.00	0.00
68	UPSW-014i	Earthing Wiring with 16 Sq.mm cable 20 KVA UPS		100.00	5.00	0.00

**Tender Code : 32821-OT**

**Supplier : V0324~M/s. Consul Neowatt Power Solutions (P) Ltd**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
1	LIA600-10	600VA LIA UPS with 10minutes backup	Make : Consul, Model: Finch-600- 12V/7AH-2nos. (Exide/Quanta/Rocket)	3,820.00	5.00	0.00
2	LIA600-30	600 VA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-600-12V/17AH-2nos. (Exide/Quanta/Rocket)	7,589.00	5.00	0.00
3	LIA1000-30	1 KVA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-!K- 12V/42AH-2nos. (Exide/Quanta/Rocket)	12,600.00	5.00	0.00
4	LIA1000-30-IC	Installation charges for 1KVA LIA UPS with 30 minutes backup		150.00	0.00	15.00
5	LIA1000-60	1 KVA LIA UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-!K- 12V/65AH-2nos. (Exide/Quanta/Rocket)	16,600.00	5.00	0.00
6	LIA1000-60-IC	Installation charges for 1KVA LIA UPS with 60 minutes backup		150.00	0.00	15.00
7	LIA1000-120	1 KVA LIA UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-!K-12V/100AH-2nos. (Exide/Quanta/Rocket)	25,350.00	5.00	0.00
8	LIA1000-120-IC	Installation charges for 1KVA LIA UPS with 120 minutes backup		150.00	0.00	15.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0324~M/s. Consul Neowatt Power Solutions (P) Ltd**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
9	LIA1000-240	1 KVA LIA UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-!K- 12V/150AH-4nos. (Exide/Quanta/Rocket)	42,850.00	5.00	0.00
10	LIA1000-240-IC	Installation charges for 1KVA LIA UPS with 240 minutes backup		150.00	0.00	15.00
11	OL1000-30	1 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-!K- 12V/26AH-3nos. (Exide/Quanta/Rocket)	16,575.00	5.00	0.00
12	OL1000-30-IC	Installation charges for 1 KVA On-Line UPS with 30 minutes backup		200.00	0.00	15.00
13	OL1000-60	1 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-!K- 12V/26AH-6nos. (Exide/Quanta/Rocket)	22,500.00	5.00	0.00
14	OL1000-60-IC	Installation charges for 1 KVA On-Line UPS with 60 minutes backup		200.00	0.00	15.00
15	OL1000-120	1 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-!K- 12V/100AH-3nos. (Exide/Quanta/Rocket)	29,249.00	5.00	0.00
16	OL1000-120-IC	Installation charges for 1 KVA On-Line UPS with 120 minutes backup		200.00	0.00	15.00
17	OL1000-240	1 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-!K- 12V/200AH-3nos. (Exide/Quanta/Rocket)	55,450.00	5.00	0.00
18	OL1000-240-IC	Installation charges for 1 KVA On-Line UPS with 240 minutes backup		200.00	0.00	15.00
19	OL2000-30	2 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-2K- 12V/26AH-6nos. (Exide/Quanta/Rocket)	28,800.00	5.00	0.00
20	OL2000-30-IC	Installation charges for 2KVA On-Line UPS with 30 minutes backup		400.00	0.00	15.00
21	OL2000-60	2 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-2K-- 12V/26AH-12nos. (Exide/Quanta/Rocket)	43,775.00	5.00	0.00
22	OL2000-60-IC	Installation charges for 2 KVA On-Line UPS with 60 minutes backup		400.00	0.00	15.00
23	OL2000-120	2 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-2K-- 12V/100AH-6nos. (Exide/Quanta/Rocket)	61,600.00	5.00	0.00
24	OL2000-120-IC	Installation charges for 2 KVA On-Line UPS with 120 minutes backup		400.00	0.00	15.00
25	OL2000-240	2 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-2K- 12V/84AH-12nos. (Exide/Quanta/Rocket)	90,550.00	5.00	0.00
26	OL2000-240-IC	Installation charges for 2 KVA On-Line UPS with 240 minutes backup		450.00	0.00	15.00
27	OL3000-30	3 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-3K- 12V/26AH-8nos. (Exide/Quanta/Rocket)	33,550.00	5.00	0.00
28	OL3000-30-IC	Installation charges for 3 KVA On-Line UPS with 30 minutes backup		450.00	0.00	15.00
29	OL3000-60	3 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-3K- 12V/65AH-6nos. (Exide/Quanta/Rocket)	51,500.00	5.00	0.00
30	OL3000-60-IC	Installation charges for 3 KVA On-Line UPS with 60 minutes backup		450.00	0.00	15.00
31	OL3000-120	3 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-3K- 12V/100AH-8nos. (Exide/Quanta/Rocket)	75,450.00	5.00	0.00
32	OL3000-120-IC	Installation charges for 3 KVA On-Line UPS with 120 minutes backup		450.00	0.00	15.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0324~M/s. Consul Neowatt Power Solutions (P) Ltd**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
33	OL3000-240	3 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-3K-12V/200AH-8nos. (Exide/Quanta/Rocket)	1,38,550.00	5.00	0.00
34	OL3000-240-IC	Installation charges for 3 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
35	OL5000-30	5 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-5K- 12V/26AH-16nos. (Exide/Quanta/Rocket)	64,475.00	5.00	0.00
36	OL5000-30-IC	Installation charges for 5 KVA On-Line UPS with 30 minutes backup	.	800.00	0.00	15.00
37	OL5000-60	5 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-5K- 12V/42AH-16nos. (Exide/Quanta/Rocket)	87,500.00	5.00	0.00
38	OL5000-60-IC	Installation charges for 5 KVA On-Line UPS with 60 minutes backup	.	800.00	0.00	15.00
39	OL5000-120	5 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-5K- 12V/84AH-16nos. (Exide/Quanta/Rocket)	1,37,200.00	5.00	0.00
40	OL5000-120-IC	Installation charges for 5 KVA On-Line UPS with 120 minutes backup	.	800.00	0.00	15.00
41	OL5000-240	5 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-5K-12V/165AH-16nos. (Exide/Quanta/Rocket)	2,37,450.00	5.00	0.00
42	OL5000-240-IC	Installation charges for 5 KVA On-Line UPS with 240 minutes backup	.	800.00	0.00	15.00
43	OL-10K-30	10 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-10K-12V/42AH-16nos. (Exide/Quanta/Rocket)	1,20,900.00	5.00	0.00
44	OL-10K-30-IC	Installation charges for 10 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
45	OL-10K-60	10 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-10K-12V/75AH-20nos. (Exide/Quanta/Rocket)	1,66,300.00	5.00	0.00
46	OL-10K-60-IC	Installation charges for 10 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
47	OL-10K-120	10 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-10K-12V/84AH-32nos. (Exide/Quanta/Rocket)	2,53,500.00	5.00	0.00
48	OL-10K-120-IC	Installation charges for 10 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
49	OL-15K-30	15 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-15K-12V/65AH-18nos. (Exide/Quanta/Rocket)	1,64,800.00	5.00	0.00
50	OL-15K-30-IC	Installation charges for 15 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
51	OL-15K-60	15 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-15K-12V/100AH-20nos. (Exide/Quanta/Rocket)	2,16,300.00	5.00	0.00
52	OL-15K-60-IC	Installation charges for 15 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
53	OL-15K-120	15 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-15K-12V/200AH-20nos. (Exide/Quanta/Rocket)	3,44,400.00	5.00	0.00
54	OL-15K-120-IC	Installation charges for 15 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
55	OL-20K-30	20 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-20K-12V/75AH-18nos. (Exide/Quanta/Rocket)	1,83,300.00	5.00	0.00
56	OL-20K-30-IC	Installation charges for 20 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00



**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0324~M/s. Consul Neowatt Power Solutions (P) Ltd**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
57	OL-20K-60	20 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-15K-12V/150AH-20nos. (Exide/Quanta/Rocket)	2,59,400.00	5.00	0.00
58	OL-20K-60-IC	Installation charges for 20 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
59	OL-20K-120	20 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Consul, Model: Finch-15K-12V/150AH-40nos. (Exide/Quanta/Rocket)	4,27,400.00	5.00	0.00
60	OL-20K-120-IC	Installation charges for 20 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
61	1151a	2 KVA UPS: Input Isolator with MS Enclosure 15-A - 2 pole		732.00	5.00	0.00
62	1151b	2 KVA UPS: Input Wiring: Cable: 2.5 Sq.mm - 2 Run & 1.5Sq.mm 1Run		98.00	5.00	0.00
63	1151c	2 KVA UPS: Output MCB with Enclosure 10 A - Double Pole		725.00	5.00	0.00
64	1151d	2 KVA UPS: Output Wiring Cable Details 2.5 Sq.mm - 3 Run		148.00	5.00	0.00
65	1152a	3 KVA UPS: Input Isolator with MS Enclosure 32-A - 2 pole		600.00	5.00	0.00
66	1152b	3 KVA UPS: Input Wiring: Cable: 4.0 Sq.mm - 2Run & 2.5 Sq.mm 1Run		168.00	5.00	0.00
67	1152c	3 KVA UPS: Output MCB with Enclosure 15 A - Double Pole		600.00	5.00	0.00
68	1152d	3 KVA UPS: Output Wiring Cable Details 2.5Sq.mm - 3 Run		148.00	5.00	0.00
69	1153a	5 KVA UPS: Input Isolator with MS Enclosure 40-A - 2 pole		790.00	5.00	0.00
70	1153b	5 KVA UPS: Input Wiring: Cable: 6.0 Sq.mm - 2 Run & 4.0 Sq.mm 1Run		247.00	5.00	0.00
71	1153c	5 KVA UPS: Output MCB with Enclosure 25 A - Double Pole		595.00	5.00	0.00
72	1153d	5KVA UPS: Output Wiring Cable Details 4.0Sq.mm - 3 Run		175.00	5.00	0.00
73	1156	5A-3pin Switches & Sockets 1 No with Gang box		145.00	5.00	0.00
74	1157	5A-3pin Switches & Sockets 1 set (1 Set = 3Nos.) with Gang box		200.00	5.00	0.00
75	1158	15A Plug & Socket with box		275.00	5.00	0.00
76	1159	Earthing for 2.0 kva & 3.0 kva		4,490.00	5.00	0.00
77	1160	Earthing for 5.0 kva		5,490.00	5.00	0.00
78	1161	Earthing Wiring with 4.0 sqmm		98.00	5.00	0.00
79	1162	Earthing wiring with 6sq.mm cable for 5.0 kva.		118.00	5.00	0.00
80	UPSW-012a	10KVA UPS - Input Isolator with MS Enclosure 32A-4 Pole		944.00	5.00	0.00
81	UPSW-012b	10KVA - Input Wiring: Cable 6.0 Sq.mm: 5 Run		283.00	5.00	0.00
82	UPSW-012c	10KVA - Output MCB with Enclosure 50A Double Pole		890.00	5.00	0.00
83	UPSW-012d	10KVA - Output Wiring Cable Details 10.0 Sq.mm 2 Run & 6.0 Sq.mm 1 Run		186.00	5.00	0.00
84	UPSW-012e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box.		148.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0324~M/s. Consul Neowatt Power Solutions (P) Ltd**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
85	UPSW-012f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
86	UPSW-012g	15A Plug & Socket with Box		248.00	5.00	0.00
87	UPSW-012h	Earthing for 10 kva - Earthing for 10 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,950.00	5.00	0.00
88	UPSW-012i	Earthing wiring with 6 sq.mm cable 10 kva ups		39.00	5.00	0.00
89	UPSW-013a	15KVA UPS - Input isolator with MS Enclosure 40A 4 Pole		1,062.00	5.00	0.00
90	UPSW-013b	15KVA UPS - Input Wiring: Cable 10.0 Sq.mm 5 Run		401.00	5.00	0.00
91	UPSW-013c	15KVA UPS - Output MCB with Enclosure 63A/80A Double Pole		1,295.00	5.00	0.00
92	UPSW-013d	15KVA UPS - Output Wiring Cable Details 25.0 Sq.mm - 2 Run & 10.0 Sq.mm 1 Run		499.00	5.00	0.00
93	UPSW-013e	Switches & Sockets 5A-3Pin Switches & Sockets 1 No. with Gang Box		150.00	5.00	0.00
94	UPSW-013f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
95	UPSW-013g	15A Plug & Socket with box		275.00	5.00	0.00
96	UPSW-013h	Earthing for 15 KVA - Earthing for 15 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		6,000.00	5.00	0.00
97	UPSW-013i	Earthing: Earthing wiring with 10 sq.mm cable 15 kva ups		71.00	5.00	0.00
98	UPSW-014a	20KVA UPS - Input Isolator with MS Enclosure 63A 4 Pole		500.00	5.00	0.00
99	UPSW-014b	20KVA UPS - Input Wiring: Cable: 16.0 Sq.mm 5 Run		625.00	5.00	0.00
100	UPSW-014c	20KVA UPS - Output MCB with Enclosure 100A Double Pole		1,000.00	5.00	0.00
101	UPSW-014d	20KVA UPS - Output Wiring Cable Details 25.0 Sq.mm 2 Run & 10.0 Sq.mm 1 Run		487.00	5.00	0.00
102	UPSW-014e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box		148.00	5.00	0.00
103	UPSW-014f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
104	UPSW-014g	15A Plug & Socket with Box		275.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0324~M/s. Consul Neowatt Power Solutions (P) Ltd**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
105	UPSW-014h	Earthing for 20 kva - Earthing for 20 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,990.00	5.00	0.00
106	UPSW-014i	Earthing Wiring with 16 Sq.mm cable 20 KVA UPS		100.00	5.00	0.00

**Tender Code : 32821-OT**

**Supplier : V0207~The Zigma Technologies India P Limited**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
1	LIA600-10	600VA LIA UPS with 10minutes backup		3,820.00	5.00	0.00
2	LIA600-30	600 VA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-LI600-30 SMF Battery 12V/26AH 2Nos (OR) 12V/42AH-1no. Exide/Quanta/Southern/Leoch/Base/Frontline	7,589.00	5.00	0.00
3	LIA1000-30	1 KVA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		12,600.00	5.00	0.00
4	LIA1000-30-IC	Installation charges for 1KVA LIA UPS with 30 minutes backup		150.00	0.00	15.00
5	LIA1000-60	1 KVA LIA UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		16,600.00	5.00	0.00
6	LIA1000-60-IC	Installation charges for 1KVA LIA UPS with 60 minutes backup		150.00	0.00	15.00
7	LIA1000-120	1 KVA LIA UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		25,350.00	5.00	0.00
8	LIA1000-120-IC	Installation charges for 1KVA LIA UPS with 120 minutes backup		150.00	0.00	15.00
9	LIA1000-240	1 KVA LIA UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.		42,850.00	5.00	0.00
10	LIA1000-240-IC	Installation charges for 1KVA LIA UPS with 240 minutes backup		150.00	0.00	15.00
11	OL1000-30	1 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-1000 SMF Battery 12V/42AH 2Nos. (OR) 12V/26AH 3nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	16,575.00	5.00	0.00
12	OL1000-30-IC	Installation charges for 1 KVA On-Line UPS with 30 minutes backup		200.00	0.00	15.00
13	OL1000-60	1 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-1000 SMF Battery 12V/65AH 2Nos. (OR) 12V/42AH 3nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	22,500.00	5.00	0.00
14	OL1000-60-IC	Installation charges for 1 KVA On-Line UPS with 60 minutes backup		200.00	0.00	15.00
15	OL1000-120	1 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-1000 SMF Battery 12V/130AH 2Nos. (OR) 12V/84AH 3nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	29,249.00	5.00	0.00



**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0207~The Zigma Technologies India P Limited**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
16	OL1000-120-IC	Installation charges for 1 KVA On-Line UPS with 120 minutes backup	.	200.00	0.00	15.00
17	OL1000-240	1 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-1000 SMF Battery 12V/100AH 6Nos. (OR) 12V/84AH 6nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	55,450.00	5.00	0.00
18	OL1000-240-IC	Installation charges for 1 KVA On-Line UPS with 240 minutes backup	.	200.00	0.00	15.00
19	OL2000-30	2 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-2000 SMF Battery 12V/26AH 6Nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	28,800.00	5.00	0.00
20	OL2000-30-IC	Installation charges for 2KVA On-Line UPS with 30 minutes backup	.	400.00	0.00	15.00
21	OL2000-60	2 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-2000 SMF Battery 12V/26AH 12Nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	43,775.00	5.00	0.00
22	OL2000-60-IC	Installation charges for 2 KVA On-Line UPS with 60 minutes backup	.	400.00	0.00	15.00
23	OL2000-120	2 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-2000 SMF Battery 12V/100AH 6Nos. (OR) 12V/75AH 8nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	61,600.00	5.00	0.00
24	OL2000-120-IC	Installation charges for 2 KVA On-Line UPS with 120 minutes backup	.	400.00	0.00	15.00
25	OL2000-240	2 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-2000 SMF Battery 12V/100AH 12Nos. (OR) 12V/130AH 8nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	90,550.00	5.00	0.00
26	OL2000-240-IC	Installation charges for 2 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
27	OL3000-30	3 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-3000 SMF Battery 12V/26AH 8Nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	33,550.00	5.00	0.00
28	OL3000-30-IC	Installation charges for 3 KVA On-Line UPS with 30 minutes backup	.	450.00	0.00	15.00
29	OL3000-60	3 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-3000 SMF Battery 12V/26AH 16Nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	51,500.00	5.00	0.00
30	OL3000-60-IC	Installation charges for 3 KVA On-Line UPS with 60 minutes backup	.	450.00	0.00	15.00
31	OL3000-120	3 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-3000 SMF Battery 12V/100AH 8Nos. (OR) 12V/84AH 10nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	75,450.00	5.00	0.00
32	OL3000-120-IC	Installation charges for 3 KVA On-Line UPS with 120 minutes backup	.	450.00	0.00	15.00
33	OL3000-240	3 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-3000 SMF Battery 12V/100AH 16Nos. (OR) 12V/84AH 20nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	1,38,550.00	5.00	0.00
34	OL3000-240-IC	Installation charges for 3 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
35	OL5000-30	5 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-5000 SMF Battery 12V/26AH 16Nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	64,475.00	5.00	0.00
36	OL5000-30-IC	Installation charges for 5 KVA On-Line UPS with 30 minutes backup	.	800.00	0.00	15.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0207~The Zigma Technologies India P Limited**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
37	OL5000-60	5 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-5000 SMF Battery 12V/42AH 16Nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	87,500.00	5.00	0.00
38	OL5000-60-IC	Installation charges for 5 KVA On-Line UPS with 60 minutes backup	.	800.00	0.00	15.00
39	OL5000-120	5 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-5000 SMF Battery 12V/42AH 32Nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	1,37,200.00	5.00	0.00
40	OL5000-120-IC	Installation charges for 5 KVA On-Line UPS with 120 minutes backup	.	800.00	0.00	15.00
41	OL5000-240	5 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-5000 SMF Battery 12V/84AH 32Nos. (OR) 12V/150AH 18nos.(OR) 12V/200AH-14nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	2,37,450.00	5.00	0.00
42	OL5000-240-IC	Installation charges for 5 KVA On-Line UPS with 240 minutes backup	.	800.00	0.00	15.00
43	OL-10K-30	10 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-10K SMF Battery 12V/42AH 16Nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	1,20,900.00	5.00	0.00
44	OL-10K-30-IC	Installation charges for 10 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
45	OL-10K-60	10 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-10K SMF Battery 12V/42AH 32Nos. (OR) 12V/84AH 16nos.(Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	1,66,300.00	5.00	0.00
46	OL-10K-60-IC	Installation charges for 10 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
47	OL-10K-120	10 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-10K SMF Battery 12V/84AH 32Nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	2,53,500.00	5.00	0.00
48	OL-10K-120-IC	Installation charges for 10 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
49	OL-15K-30	15 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-15K SMF Battery 12V/65AH 16Nos. (OR) 12V/42AH 24nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	1,64,800.00	5.00	0.00
50	OL-15K-30-IC	Installation charges for 15 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
51	OL-15K-60	15 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-15K SMF Battery 12V/84AH 24Nos. (OR) 12V/75AH 27nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	2,16,300.00	5.00	0.00
52	OL-15K-60-IC	Installation charges for 15 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
53	OL-15K-120	15 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-15K SMF Battery 12V/84AH 48Nos. (OR) 12V/150AH 27nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	3,44,400.00	5.00	0.00
54	OL-15K-120-IC	Installation charges for 15 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
55	OL-20K-30	20 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-20K SMF Battery 12V/65AH 30Nos. (OR) 12V/26AH 60nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	1,83,300.00	5.00	0.00
56	OL-20K-30-IC	Installation charges for 20 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0207~The Zigma Technologies India P Limited**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
57	OL-20K-60	20 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : FrontlineModel : FSS-20K SMF Battery 12V/100AH 30Nos. (OR) 12V/84AH 32nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	2,59,400.00	5.00	0.00
58	OL-20K-60-IC	Installation charges for 20 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
59	OL-20K-120	20 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : FrontlineModel : FSS-20K SMF Battery 12V/200AH 30Nos. (OR) 12V/84AH 64nos. (Exide/Quanta/Southern/Leoch/Base/Frontline/U-Plus)	4,27,400.00	5.00	0.00
60	OL-20K-120-IC	Installation charges for 20 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
61	1151a	2 KVA UPS: Input Isolator with MS Enclosure 15-A - 2 pole		732.00	5.00	0.00
62	1151b	2 KVA UPS: Input Wiring: Cable: 2.5 Sq.mm - 2 Run & 1.5Sq.mm 1Run		98.00	5.00	0.00
63	1151c	2 KVA UPS: Output MCB with Enclosure 10 A - Double Pole		725.00	5.00	0.00
64	1151d	2 KVA UPS: Output Wiring Cable Details2.5 Sq.mm - 3 Run		148.00	5.00	0.00
65	1152a	3 KVA UPS: InputIsolator with MS Enclosure32-A - 2 pole		600.00	5.00	0.00
66	1152b	3 KVA UPS: InputWiring: Cable: 4.0 Sq.mm - 2Run & 2.5 Sq.mm 1Run		168.00	5.00	0.00
67	1152c	3 KVA UPS: Output MCBwith Enclosure15 A - Double Pole		600.00	5.00	0.00
68	1152d	3 KVA UPS: Output WiringCable Details 2.5Sq.mm - 3 Run		148.00	5.00	0.00
69	1153a	5 KVA UPS: InputIsolator with MS Enclosure40-A - 2 pole		790.00	5.00	0.00
70	1153b	5 KVA UPS: Input Wiring:Cable: 6.0 Sq.mm - 2 Run & 4.0 Sq.mm 1Run		247.00	5.00	0.00
71	1153c	5 KVA UPS: Output MCBwith Enclosure 25 A - DoublePole		595.00	5.00	0.00
72	1153d	5KVA UPS: Output WiringCable Details 4.0Sq.mm - 3 Run		175.00	5.00	0.00
73	1156	5A-3pin Switches &Sockets 1 No with Gang box		145.00	5.00	0.00
74	1157	5A-3pin Switches &Sockets 1 set (1 Set = 3Nos.) with Gang box		200.00	5.00	0.00
75	1158	15A Plug & Socket with box		275.00	5.00	0.00
76	1159	Earthing for 2.0 kva &3.0 kva		4,490.00	5.00	0.00
77	1160	Earthing for 5.0 kva		5,490.00	5.00	0.00
78	1161	Earthing Wiring with4.0 sqmm		98.00	5.00	0.00
79	1162	Earthing wiring with 6sq.mm cable for 5.0 kva.		118.00	5.00	0.00
80	UPSW-012a	10KVA UPS - Input Isolator with MS Enclosure 32A-4 Pole		944.00	5.00	0.00
81	UPSW-012b	10KVA - Input Wiring: Cable 6.0 Sq.mm: 5 Run		283.00	5.00	0.00
82	UPSW-012c	10KVA - Output MCB with Enclosure 50A Double Pole		890.00	5.00	0.00
83	UPSW-012d	10KVA - Output Wiring Cable Details 10.0 Sq.mm 2 Run & 6.0 Sq.mm 1 Run		186.00	5.00	0.00



**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0207~The Zigma Technologies India P Limited**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
84	UPSW-012e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box.		148.00	5.00	0.00
85	UPSW-012f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
86	UPSW-012g	15A Plug & Socket with Box		248.00	5.00	0.00
87	UPSW-012h	Earthing for 10 kva - Earthing for 10 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,950.00	5.00	0.00
88	UPSW-012i	Earthing wiring with 6 sq.mm cable 10 kva ups		39.00	5.00	0.00
89	UPSW-013a	15KVA UPS - Input isolator with MS Enclosure 40A 4 Pole		1,062.00	5.00	0.00
90	UPSW-013b	15KVA UPS - Input Wiring: Cable 10.0 Sq.mm 5 Run		401.00	5.00	0.00
91	UPSW-013c	15KVA UPS - Output MCB with Enclosure 63A/80A Double Pole		1,295.00	5.00	0.00
92	UPSW-013d	15KVA UPS - Output Wiring Cable Details 25.0 Sq.mm - 2 Run & 10.0 Sq.mm 1 Run		499.00	5.00	0.00
93	UPSW-013e	Switches & Sockets 5A-3Pin Switches & Sockets 1 No. with Gang Box		150.00	5.00	0.00
94	UPSW-013f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
95	UPSW-013g	15A Plug & Socket with box		275.00	5.00	0.00
96	UPSW-013h	Earthing for 15 KVA - Earthing for 15 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		6,000.00	5.00	0.00
97	UPSW-013i	Earthing: Earthing wiring with 10 sq.mm cable 15 kva ups		71.00	5.00	0.00
98	UPSW-014a	20KVA UPS - Input Isolator with MS Enclosure 63A 4 Pole		500.00	5.00	0.00
99	UPSW-014b	20KVA UPS - Input Wiring: Cable: 16.0 Sq.mm 5 Run		625.00	5.00	0.00
100	UPSW-014c	20KVA UPS - Output MCB with Enclosure 100A Double Pole		1,000.00	5.00	0.00
101	UPSW-014d	20KVA UPS - Output Wiring Cable Details 25.0 Sq.mm 2 Run & 10.0 Sq.mm 1 Run		487.00	5.00	0.00
102	UPSW-014e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box		148.00	5.00	0.00
103	UPSW-014f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0207~The Zigma Technologies India P Limited**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
104	UPSW-014g	15A Plug & Socket with Box		275.00	5.00	0.00
105	UPSW-014h	Earthing for 20 kva - Earthing for 20 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,990.00	5.00	0.00
106	UPSW-014i	Earthing Wiring with 16 Sq.mm cable 20 KVA UPS		100.00	5.00	0.00

**Tender Code : 32821-OT**

**Supplier : V0213~JR COMMUNICATIONS & POWER CONTROLS PVT LTD**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
1	LIA600-10	600VA LIA UPS with 10minutes backup	Make : RPC, Model : LIA 600-1012V/9AH 1No. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	3,820.00	5.00	0.00
2	LIA600-30	600 VA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model : LIA 600-3012V/42AH 1No. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket) Make : RPC, Model : LIA 600-3012V/42AH 1No. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	7,589.00	5.00	0.00
3	LIA1000-30	1 KVA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model : LIA 1000-3012V/26AH 3Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	12,600.00	5.00	0.00
4	LIA1000-30-IC	Installation charges for 1KVA LIA UPS with 30 minutes backup		150.00	0.00	15.00
5	LIA1000-60	1 KVA LIA UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model : LIA 1000-6012V/42AH 3Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	16,600.00	5.00	0.00
6	LIA1000-60-IC	Installation charges for 1KVA LIA UPS with 60 minutes backup		150.00	0.00	15.00
7	LIA1000-120	1 KVA LIA UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model : LIA 1000-12012V/84AH 3Nos. (OR) 12V/42AH 6nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	25,350.00	5.00	0.00
8	LIA1000-120-IC	Installation charges for 1KVA LIA UPS with 120 minutes backup		150.00	0.00	15.00
9	LIA1000-240	1 KVA LIA UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model : LIA 1000-24012V/84AH 6Nos. (OR) 12V/42AH 12nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	42,850.00	5.00	0.00
10	LIA1000-240-IC	Installation charges for 1KVA LIA UPS with 240 minutes backup		150.00	0.00	15.00
11	OL1000-30	1 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model : OL 1000-3012V/26AH 3Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	16,575.00	5.00	0.00
12	OL1000-30-IC	Installation charges for 1 KVA On-Line UPS with 30 minutes backup		200.00	0.00	15.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0213~JR COMMUNICATIONS & POWER CONTROLS PVT LTD**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
13	OL1000-60	1 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model : OL 1000-6012V/42AH 3Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	22,500.00	5.00	0.00
14	OL1000-60-IC	Installation charges for 1 KVA On-Line UPS with 60 minutes backup	.	200.00	0.00	15.00
15	OL1000-120	1 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model : OL 1000-12012V/84AH 3Nos. (OR) 12V/42AH 6nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	29,249.00	5.00	0.00
16	OL1000-120-IC	Installation charges for 1 KVA On-Line UPS with 120 minutes backup	.	200.00	0.00	15.00
17	OL1000-240	1 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model :OL 1000-24012V/200AH 3Nos. (OR) 12V/84AH 6nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	55,450.00	5.00	0.00
18	OL1000-240-IC	Installation charges for 1 KVA On-Line UPS with 240 minutes backup	.	200.00	0.00	15.00
19	OL2000-30	2 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model : OL 2000-3012V/26AH 5Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	28,800.00	5.00	0.00
20	OL2000-30-IC	Installation charges for 2KVA On-Line UPS with 30 minutes backup	.	400.00	0.00	15.00
21	OL2000-60	2 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model : OL 2000-6012V/42AH 7Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	43,775.00	5.00	0.00
22	OL2000-60-IC	Installation charges for 2 KVA On-Line UPS with 60 minutes backup	.	400.00	0.00	15.00
23	OL2000-120	2 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model : OL 2000-12012V/75AH 7Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	61,600.00	5.00	0.00
24	OL2000-120-IC	Installation charges for 2 KVA On-Line UPS with 120 minutes backup	.	400.00	0.00	15.00
25	OL2000-240	2 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model :OL 2000-24012V/130AH 8Nos. (OR) 12V/65AH 16nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	90,550.00	5.00	0.00
26	OL2000-240-IC	Installation charges for 2 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
27	OL3000-30	3 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model : OL 3000-3012V/26AH 7Nos. (OR) 12V/28AH - 7nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	33,550.00	5.00	0.00
28	OL3000-30-IC	Installation charges for 3 KVA On-Line UPS with 30 minutes backup	.	450.00	0.00	15.00
29	OL3000-60	3 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model : OL 3000-6012V/65AH 6Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	51,500.00	5.00	0.00
30	OL3000-60-IC	Installation charges for 3 KVA On-Line UPS with 60 minutes backup	.	450.00	0.00	15.00
31	OL3000-120	3 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model : OL 3000-12012V/100AH 8Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	75,450.00	5.00	0.00
32	OL3000-120-IC	Installation charges for 3 KVA On-Line UPS with 120 minutes backup	.	450.00	0.00	15.00



**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0213~JR COMMUNICATIONS & POWER CONTROLS PVT LTD**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
33	OL3000-240	3 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model :OL 3000-24012V/200AH 8Nos. (OR) 12V/100AH 16nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	1,38,550.00	5.00	0.00
34	OL3000-240-IC	Installation charges for 3 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
35	OL5000-30	5 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model : OL 5000-3012V/42AH 8Nos.SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	64,475.00	5.00	0.00
36	OL5000-30-IC	Installation charges for 5 KVA On-Line UPS with 30 minutes backup	.	800.00	0.00	15.00
37	OL5000-60	5 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model : OL 5000-6012V/84AH 8Nos. (OR) 12V/42AH 16nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	87,500.00	5.00	0.00
38	OL5000-60-IC	Installation charges for 5 KVA On-Line UPS with 60 minutes backup	.	800.00	0.00	15.00
39	OL5000-120	5 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model : OL 5000-12012V/65AH 21Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	1,37,200.00	5.00	0.00
40	OL5000-120-IC	Installation charges for 5 KVA On-Line UPS with 120 minutes backup	.	800.00	0.00	15.00
41	OL5000-240	5 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model :OL 5000-24012V/130AH 21Nos. (OR) 12V/65AH 42nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	2,37,450.00	5.00	0.00
42	OL5000-240-IC	Installation charges for 5 KVA On-Line UPS with 240 minutes backup	.	800.00	0.00	15.00
43	OL-10K-30	10 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model :OL 10K-3012V/42AH 16Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	1,20,900.00	5.00	0.00
44	OL-10K-30-IC	Installation charges for 10 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
45	OL-10K-60	10 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model :OL 10K-6012V/65AH 21Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	1,66,300.00	5.00	0.00
46	OL-10K-60-IC	Installation charges for 10 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
47	OL-10K-120	10 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model :OL 10K-12012V/130AH 21Nos. (OR) 12V/65AH-42nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	2,53,500.00	5.00	0.00
48	OL-10K-120-IC	Installation charges for 10 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
49	OL-15K-30	15 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model :OL 15K-3012V/65AH 16Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	1,64,800.00	5.00	0.00
50	OL-15K-30-IC	Installation charges for 15 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
51	OL-15K-60	15 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model :OL 15K-6012V/100AH 20Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	2,16,300.00	5.00	0.00
52	OL-15K-60-IC	Installation charges for 15 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0213~JR COMMUNICATIONS & POWER CONTROLS PVT LTD**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
53	OL-15K-120	15 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model :OL 15K-12012V/200AH 20Nos. (OR) 12V/100AH 40nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	3,44,400.00	5.00	0.00
54	OL-15K-120-IC	Installation charges for 15 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
55	OL-20K-30	20 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model :OL 20K-3012V/65AH 21Nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	1,83,300.00	5.00	0.00
56	OL-20K-30-IC	Installation charges for 20 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
57	OL-20K-60	20 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : RPC, Model :OL 20K-6012V/130AH 21Nos. (OR) 12V/65AH-42nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	2,59,400.00	5.00	0.00
58	OL-20K-60-IC	Installation charges for 20 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
59	OL-20K-120	20 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : RPC, Model :OL 20K-12012V/200AH 27Nos. (OR) 12V/100AH 54nos. SMF battery (Amaron Quanta/Exide/Exide-SF/Rocket)	4,27,400.00	5.00	0.00
60	OL-20K-120-IC	Installation charges for 20 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
61	1151a	2 KVA UPS: Input Isolator with MS Enclosure 15-A - 2 pole		732.00	5.00	0.00
62	1151b	2 KVA UPS: Input Wiring: Cable: 2.5 Sq.mm - 2 Run & 1.5Sq.mm 1Run		98.00	5.00	0.00
63	1151c	2 KVA UPS: Output MCB with Enclosure 10 A - Double Pole		725.00	5.00	0.00
64	1151d	2 KVA UPS: Output Wiring Cable Details 2.5 Sq.mm - 3 Run		148.00	5.00	0.00
65	1152a	3 KVA UPS: Input Isolator with MS Enclosure 32-A - 2 pole		600.00	5.00	0.00
66	1152b	3 KVA UPS: Input Wiring: Cable: 4.0 Sq.mm - 2Run & 2.5 Sq.mm 1Run		168.00	5.00	0.00
67	1152c	3 KVA UPS: Output MCB with Enclosure 15 A - Double Pole		600.00	5.00	0.00
68	1152d	3 KVA UPS: Output Wiring Cable Details 2.5Sq.mm - 3 Run		148.00	5.00	0.00
69	1153a	5 KVA UPS: Input Isolator with MS Enclosure 40-A - 2 pole		790.00	5.00	0.00
70	1153b	5 KVA UPS: Input Wiring: Cable: 6.0 Sq.mm - 2 Run & 4.0 Sq.mm 1Run		247.00	5.00	0.00
71	1153c	5 KVA UPS: Output MCB with Enclosure 25 A - Double Pole		595.00	5.00	0.00
72	1153d	5KVA UPS: Output Wiring Cable Details 4.0Sq.mm - 3 Run		175.00	5.00	0.00
73	1156	5A-3pin Switches & Sockets 1 No with Gang box		145.00	5.00	0.00
74	1157	5A-3pin Switches & Sockets 1 set (1 Set = 3Nos.) with Gang box		200.00	5.00	0.00
75	1158	15A Plug & Socket with box		275.00	5.00	0.00
76	1159	Earthing for 2.0 kva & 3.0 kva		4,490.00	5.00	0.00
77	1160	Earthing for 5.0 kva		5,490.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0213~JR COMMUNICATIONS & POWER CONTROLS PVT LTD**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
78	1161	Earthing Wiring with 4.0 sqmm		98.00	5.00	0.00
79	1162	Earthing wiring with 6sq.mm cable for 5.0 kva.		118.00	5.00	0.00
80	UPSW-012a	10KVA UPS - Input Isolator with MS Enclosure 32A-4 Pole		944.00	5.00	0.00
81	UPSW-012b	10KVA - Input Wiring: Cable 6.0 Sq.mm: 5 Run		283.00	5.00	0.00
82	UPSW-012c	10KVA - Output MCB with Enclosure 50A Double Pole		890.00	5.00	0.00
83	UPSW-012d	10KVA - Output Wiring Cable Details 10.0 Sq.mm 2 Run & 6.0 Sq.mm 1 Run		186.00	5.00	0.00
84	UPSW-012e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box.		148.00	5.00	0.00
85	UPSW-012f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
86	UPSW-012g	15A Plug & Socket with Box		248.00	5.00	0.00
87	UPSW-012h	Earthing for 10 kva - Earthing for 10 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,950.00	5.00	0.00
88	UPSW-012i	Earthing wiring with 6 sq.mm cable 10 kva ups		39.00	5.00	0.00
89	UPSW-013a	15KVA UPS - Input isolator with MS Enclosure 40A 4 Pole		1,062.00	5.00	0.00
90	UPSW-013b	15KVA UPS - Input Wiring: Cable 10.0 Sq.mm 5 Run		401.00	5.00	0.00
91	UPSW-013c	15KVA UPS - Output MCB with Enclosure 63A/80A Double Pole		1,295.00	5.00	0.00
92	UPSW-013d	15KVA UPS - Output Wiring Cable Details 25.0 Sq.mm - 2 Run & 10.0 Sq.mm 1 Run		499.00	5.00	0.00
93	UPSW-013e	Switches & Sockets 5A-3Pin Switches & Sockets 1 No. with Gang Box		150.00	5.00	0.00
94	UPSW-013f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
95	UPSW-013g	15A Plug & Socket with box		275.00	5.00	0.00
96	UPSW-013h	Earthing for 15 KVA - Earthing for 15 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		6,000.00	5.00	0.00
97	UPSW-013i	Earthing: Earthing wiring with 10 sq.mm cable 15 kva ups		71.00	5.00	0.00



**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0213~JR COMMUNICATIONS & POWER CONTROLS PVT LTD**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
98	UPSW-014a	20KVA UPS - Input Isolator with MS Enclosure 63A 4 Pole		500.00	5.00	0.00
99	UPSW-014b	20KVA UPS - Input Wiring: Cable: 16.0 Sq.mm 5 Run		625.00	5.00	0.00
100	UPSW-014c	20KVA UPS - Output MCB with Enclosure 100A Double Pole		1,000.00	5.00	0.00
101	UPSW-014d	20KVA UPS - Output Wiring Cable Details 25.0 Sq.mm 2 Run & 10.0 Sq.mm 1 Run		487.00	5.00	0.00
102	UPSW-014e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box		148.00	5.00	0.00
103	UPSW-014f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
104	UPSW-014g	15A Plug & Socket with Box		275.00	5.00	0.00
105	UPSW-014h	Earthing for 20 kva - Earthing for 20 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,990.00	5.00	0.00
106	UPSW-014i	Earthing Wiring with 16 Sq.mm cable 20 KVA UPS		100.00	5.00	0.00

**Tender Code : 32821-OT**

**Supplier : V0248~Bharat Power Solutions**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
1	LIA600-10	600VA LIA UPS with 10minutes backup	Make : Hitachi Hirel, Model : IP LI600 SMF Battery - 12V/7AH 2Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	3,820.00	5.00	0.00
2	LIA600-30	600 VA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP LI600 SMF Battery 12V/18H 2Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	7,589.00	5.00	0.00
3	LIA1000-30	1 KVA LIA UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Hitachi Hirel, Model : IP LI1000 SMF Battery - 12V/42AH 2Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower).	12,600.00	5.00	0.00
4	LIA1000-30-IC	Installation charges for 1KVA LIA UPS with 30 minutes backup		150.00	0.00	15.00
5	LIA1000-60	1 KVA LIA UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP LI1000 SMF Battery 12V/65AH 2Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	16,600.00	5.00	0.00
6	LIA1000-60-IC	Installation charges for 1KVA LIA UPS with 60 minutes backup		150.00	0.00	15.00
7	LIA1000-120	1 KVA LIA UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP LI1000 SMF Battery - 12V/65AH 4Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	25,350.00	5.00	0.00
8	LIA1000-120-IC	Installation charges for 1KVA LIA UPS with 120 minutes backup		150.00	0.00	15.00
9	LIA1000-240	1 KVA LIA UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed)	. Make : Hitachi Hirel, Model : IP LI1000 SMF Battery - 12V/130AH 4Nos	42,850.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0248~Bharat Power Solutions**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
		battery back up.	(Rocket/Exide/ Quanta/Leoch/Panasonic/Hipower)			
10	LIA1000-240-IC	Installation charges for 1KVA LIA UPS with 240 minutes backup		150.00	0.00	15.00
11	OL1000-30	1 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-1 SMF Battery - 12V/26AH 3Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	16,575.00	5.00	0.00
12	OL1000-30-IC	Installation charges for 1 KVA On-Line UPS with 30 minutes backup	.	200.00	0.00	15.00
13	OL1000-60	1 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-1 SMF Battery 12V/45AH 3Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	22,500.00	5.00	0.00
14	OL1000-60-IC	Installation charges for 1 KVA On-Line UPS with 60 minutes backup	.	200.00	0.00	15.00
15	OL1000-120	1 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-1 SMF Battery - 12V/42AH 6Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	29,249.00	5.00	0.00
16	OL1000-120-IC	Installation charges for 1 KVA On-Line UPS with 120 minutes backup	.	200.00	0.00	15.00
17	OL1000-240	1 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-1 SMF Battery - 12V/100AH 6Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	55,450.00	5.00	0.00
18	OL1000-240-IC	Installation charges for 1 KVA On-Line UPS with 240 minutes backup	.	200.00	0.00	15.00
19	OL2000-30	2 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-2 SMF Battery 12V/42AH 4Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	28,800.00	5.00	0.00
20	OL2000-30-IC	Installation charges for 2KVA On-Line UPS with 30 minutes backup	.	400.00	0.00	15.00
21	OL2000-60	2 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-2 SMF Battery 12V/75AH 4Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	43,775.00	5.00	0.00
22	OL2000-60-IC	Installation charges for 2 KVA On-Line UPS with 60 minutes backup	.	400.00	0.00	15.00
23	OL2000-120	2 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-2 SMF Battery 12V/75AH 8Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	61,600.00	5.00	0.00
24	OL2000-120-IC	Installation charges for 2 KVA On-Line UPS with 120 minutes backup	.	400.00	0.00	15.00
25	OL2000-240	2 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-2 SMF Battery 12V/130AH 8Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	90,550.00	5.00	0.00
26	OL2000-240-IC	Installation charges for 2 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
27	OL3000-30	3 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-3 SMF Battery 12V/42AH 6Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	33,550.00	5.00	0.00
28	OL3000-30-IC	Installation charges for 3 KVA On-Line UPS with 30 minutes backup	.	450.00	0.00	15.00
29	OL3000-60	3 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-3 SMF Battery 12V/75AH 6Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	51,500.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0248~Bharat Power Solutions**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
30	OL3000-60-IC	Installation charges for 3 KVA On-Line UPS with 60 minutes backup	.	450.00	0.00	15.00
31	OL3000-120	3 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-3 SMF Battery 12V/75AH 12Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	75,450.00	5.00	0.00
32	OL3000-120-IC	Installation charges for 3 KVA On-Line UPS with 120 minutes backup	.	450.00	0.00	15.00
33	OL3000-240	3 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-3 SMF Battery 12V/150AH 12Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	1,38,550.00	5.00	0.00
34	OL3000-240-IC	Installation charges for 3 KVA On-Line UPS with 240 minutes backup	.	450.00	0.00	15.00
35	OL5000-30	5 KVA On-Line UPS with 30 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-5 SMF Battery 12V/26AH 16Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	64,475.00	5.00	0.00
36	OL5000-30-IC	Installation charges for 5 KVA On-Line UPS with 30 minutes backup	.	800.00	0.00	15.00
37	OL5000-60	5 KVA On-Line UPS with 60 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-5 SMF Battery 12V/42AH 16Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	87,500.00	5.00	0.00
38	OL5000-60-IC	Installation charges for 5 KVA On-Line UPS with 60 minutes backup	.	800.00	0.00	15.00
39	OL5000-120	5 KVA On-Line UPS with 120 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-5 SMF Battery 12V/84AH 16Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	1,37,200.00	5.00	0.00
40	OL5000-120-IC	Installation charges for 5 KVA On-Line UPS with 120 minutes backup	.	800.00	0.00	15.00
41	OL5000-240	5 KVA On-Line UPS with 240 minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 11-5 SMF Battery 12V/84AH 32Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	2,37,450.00	5.00	0.00
42	OL5000-240-IC	Installation charges for 5 KVA On-Line UPS with 240 minutes backup	.	800.00	0.00	15.00
43	OL-10K-30	10 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 31-10 SMF Battery 12V/35AH 20Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	1,20,900.00	5.00	0.00
44	OL-10K-30-IC	Installation charges for 10 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
45	OL-10K-60	10 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Hitachi Hirel, Model : IP 31-10 SMF Battery 12V/75AH 20Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	1,66,300.00	5.00	0.00
46	OL-10K-60-IC	Installation charges for 10 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
47	OL-10K-120	10 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Hitachi Hirel, Model : IP 31-10 SMF Battery 12V/150AH 20Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	2,53,500.00	5.00	0.00
48	OL-10K-120-IC	Installation charges for 10 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
49	OL-15K-30	15 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Hitachi Hirel, Model : IP 31-15 SMF Battery 12V/65AH 20Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	1,64,800.00	5.00	0.00
50	OL-15K-30-IC	Installation charges for 15 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00



**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0248~Bharat Power Solutions**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
51	OL-15K-60	15 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Hitachi Hirel, Model : IP 31-15 SMF Battery 12V/100AH 20Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	2,16,300.00	5.00	0.00
52	OL-15K-60-IC	Installation charges for 15 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
53	OL-15K-120	15 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Hitachi Hirel, Model : IP 31-15 SMF Battery 12V/100AH 40Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	3,44,400.00	5.00	0.00
54	OL-15K-120-IC	Installation charges for 15 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
55	OL-20K-30	20 KVA Online UPS Systems 30 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 31-20 SMF Battery 12V/75AH 20Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	1,83,300.00	5.00	0.00
56	OL-20K-30-IC	Installation charges for 20 KVA Online UPS Systems 30 Minutes Backup	.	800.00	0.00	15.00
57	OL-20K-60	20 KVA Online UPS Systems 60 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	. Make : Hitachi Hirel, Model : IP 31-20 SMF Battery 12V/150AH 20Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	2,59,400.00	5.00	0.00
58	OL-20K-60-IC	Installation charges for 20 KVA Online UPS Systems 60 Minutes Backup	.	800.00	0.00	15.00
59	OL-20K-120	20 KVA Online UPS Systems 120 Minutes SMF (Panasonic / Exide /Base or any reputed) battery back up.	Make : Hitachi Hirel, Model : IP 31-20 SMF Battery 12V/150AH 40Nos (Rocket/Exide/Quanta/Leoch/Panasonic/Hipower)	4,27,400.00	5.00	0.00
60	OL-20K-120-IC	Installation charges for 20 KVA Online UPS Systems 120 Minutes Backup	.	800.00	0.00	15.00
61	1151a	2 KVA UPS: Input Isolator with MS Enclosure 15-A - 2 pole		732.00	5.00	0.00
62	1151b	2 KVA UPS: Input Wiring: Cable: 2.5 Sq.mm - 2 Run & 1.5Sq.mm 1Run		98.00	5.00	0.00
63	1151c	2 KVA UPS: Output MCB with Enclosure 10 A - Double Pole		725.00	5.00	0.00
64	1151d	2 KVA UPS: Output Wiring Cable Details 2.5 Sq.mm - 3 Run		148.00	5.00	0.00
65	1152a	3 KVA UPS: Input Isolator with MS Enclosure 32-A - 2 pole		600.00	5.00	0.00
66	1152b	3 KVA UPS: Input Wiring: Cable: 4.0 Sq.mm - 2Run & 2.5 Sq.mm 1Run		168.00	5.00	0.00
67	1152c	3 KVA UPS: Output MCB with Enclosure 15 A - Double Pole		600.00	5.00	0.00
68	1152d	3 KVA UPS: Output Wiring Cable Details 2.5Sq.mm - 3 Run		148.00	5.00	0.00
69	1153a	5 KVA UPS: Input Isolator with MS Enclosure 40-A - 2 pole		790.00	5.00	0.00
70	1153b	5 KVA UPS: Input Wiring: Cable: 6.0 Sq.mm - 2 Run & 4.0 Sq.mm 1Run		247.00	5.00	0.00
71	1153c	5 KVA UPS: Output MCB with Enclosure 25 A - Double Pole		595.00	5.00	0.00
72	1153d	5KVA UPS: Output Wiring Cable Details 4.0Sq.mm - 3 Run		175.00	5.00	0.00
73	1156	5A-3pin Switches & Sockets 1 No with Gang box		145.00	5.00	0.00
74	1157	5A-3pin Switches & Sockets 1 set (1 Set = 3Nos.) with Gang box		200.00	5.00	0.00
75	1158	15A Plug & Socket with box		275.00	5.00	0.00

**Tender Details**

Tender Code : 32821-OT

Supplier : V0248~Bharat Power Solutions

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
76	1159	Earthing for 2.0 kva & 3.0 kva		4,490.00	5.00	0.00
77	1160	Earthing for 5.0 kva		5,490.00	5.00	0.00
78	1161	Earthing Wiring with 4.0 sqmm		98.00	5.00	0.00
79	1162	Earthing wiring with 6sq.mm cable for 5.0 kva.		118.00	5.00	0.00
80	UPSW-012a	10KVA UPS - Input Isolator with MS Enclosure 32A-4 Pole		944.00	5.00	0.00
81	UPSW-012b	10KVA - Input Wiring: Cable 6.0 Sq.mm: 5 Run		283.00	5.00	0.00
82	UPSW-012c	10KVA - Output MCB with Enclosure 50A Double Pole		890.00	5.00	0.00
83	UPSW-012d	10KVA - Output Wiring Cable Details 10.0 Sq.mm 2 Run & 6.0 Sq.mm 1 Run		186.00	5.00	0.00
84	UPSW-012e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box.		148.00	5.00	0.00
85	UPSW-012f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
86	UPSW-012g	15A Plug & Socket with Box		248.00	5.00	0.00
87	UPSW-012h	Earthing for 10 kva - Earthing for 10 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,950.00	5.00	0.00
88	UPSW-012i	Earthing wiring with 6 sq.mm cable 10 kva ups		39.00	5.00	0.00
89	UPSW-013a	15KVA UPS - Input isolator with MS Enclosure 40A 4 Pole		1,062.00	5.00	0.00
90	UPSW-013b	15KVA UPS - Input Wiring: Cable 10.0 Sq.mm 5 Run		401.00	5.00	0.00
91	UPSW-013c	15KVA UPS - Output MCB with Enclosure 63A/80A Double Pole		1,295.00	5.00	0.00
92	UPSW-013d	15KVA UPS - Output Wiring Cable Details 25.0 Sq.mm - 2 Run & 10.0 Sq.mm 1 Run		499.00	5.00	0.00
93	UPSW-013e	Switches & Sockets 5A-3Pin Switches & Sockets 1 No. with Gang Box		150.00	5.00	0.00
94	UPSW-013f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
95	UPSW-013g	15A Plug & Socket with box		275.00	5.00	0.00
96	UPSW-013h	Earthing for 15 KVA - Earthing for 15 kva - Providing separate Isolated Earth pit. Earth pit - 2" x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		6,000.00	5.00	0.00

**Tender Details**

**Tender Code : 32821-OT**

**Supplier : V0248~Bharat Power Solutions**

S.No.	Item Code	Item Description	Item Configuration	Unit Price (Rs)	VAT (%)	Service Tax (%)
97	UPSW-013i	Earthing: Earthing wiring with 10 sq.mm cable 15 kva ups		71.00	5.00	0.00
98	UPSW-014a	20KVA UPS - Input Isolator with MS Enclosure 63A 4 Pole		500.00	5.00	0.00
99	UPSW-014b	20KVA UPS - Input Wiring: Cable: 16.0 Sq.mm 5 Run		625.00	5.00	0.00
100	UPSW-014c	20KVA UPS - Output MCB with Enclosure 100A Double Pole		1,000.00	5.00	0.00
101	UPSW-014d	20KVA UPS - Output Wiring Cable Details 25.0 Sq.mm 2 Run & 10.0 Sq.mm 1 Run		487.00	5.00	0.00
102	UPSW-014e	Switches & Sockets: 5A-3Pin Switches & Sockets 1 No. with Gang Box		148.00	5.00	0.00
103	UPSW-014f	5A-3Pin Switches & Sockets 1 Set with Gang Box		150.00	5.00	0.00
104	UPSW-014g	15A Plug & Socket with Box		275.00	5.00	0.00
105	UPSW-014h	Earthing for 20 kva - Earthing for 20 kva - Providing separate Isolated Earth pit. Earth pit - 2' x 10 feet deep digging and providing 38mm G.I. pipe to a depth of 2.8Mts from the ground level and running copper strip from ground level to termination end, and filling of Charcoal and salt all among the earth Electrode up to ground level. The top end of the G.I. pipe should be provided with funnel and copper bar. (including Civil work)		5,990.00	5.00	0.00
106	UPSW-014i	Earthing Wiring with 16 Sq.mm cable 20 KVA UPS		100.00	5.00	0.00